

HDDSIV

Vertical hinged joiner for HDKLIE



The hinge slides +/- 110 mm over the cable ladder.

Reference	↕ mm	↔ mm	→ ← mm	↔ mm	kg/stk	📦	Unit
HDDSIV	90				1,040	4	STK

Premounted with tapbolt 6x12.